

# RISK ASSESSMENT

Assessment Title (Task, process, equipment or facility)		VNA-MAST REMOVAL-INSTALLATION		Location	Customer Premises/Toyota Workshops
Date	01/04/2026	Prepared By	R Lewis, M Ockwell	This is in addition to generic risk assessments available	
Review Date	31/03/2027				
Service Order Number/s				On Site Rules to be adhered to at all times	
<p>Specific training is supplied via the TMHUK training Programmes</p> <p>Including: General H&amp;S, Working at Height, Use and Maintenance of Lifting Equipment &amp; Tools, Selection of Safe Working Area, Jacking &amp; Blocking, Use of PPE</p>					

Hazards. Identify all hazards from this activity. Select from the list below what could cause harm from this activity <i>E.G working at height, trip hazard. Etc</i>	Effect (Who/what may be harmed/damaged?)	Potential injury/effect sustained	Initial Risk			Current Control Measures <small>For each hazard, the measures taken by TMHUK to minimise the risk identified</small>	Risk <small>The level of risk once current controls are in place</small>			Additional Controls Measures <small>For each hazard, list any site specific measures you will be taking to further minimise the risk identified</small>	Action by whom?	Action by when?
			Likelihood	Severity	Risk Level		Likelihood	Severity	Risk Level			
Work Area	TMHUK Team Members/ customer / 3rd party contractors / site visitors	Various injuries to the human physique / respiratory problems/ crushing & trapping injuries	3	4	M	1. All recognised work processes carried out on customer premises will be assessed & treated in a similar fashion before proceeding with the job activity. Refer to Safe Working Practice (SWP 01-Work Area) 2. Working in busy, exposed areas e.g. warehouse aisles should be avoided & only attempted when no other option is available. Suitable provision to make the work area safe must be available. 3. Work areas must be protected from moving vehicles.	1	4	L	PARTICULAR ATTENTION SHOULD BE MADE TO OVERHEAD CLEARANCE WITH CRANES OR LIFT TRUCK. SUITABLE SURROUNDING AREA MUST BE CLEAR OF ALL OBSTRUCTIONSAND UNAUTHORISED PERSONS	BANKSMAN OR LEAD PERSON. MUST BE DECIDED PRIOR TO START OF WORK	INSTALL DAY
Harness/ Lanyard -Use of	TMHUK Team Members	Various injuries to the human physique / possibility of death	3	5	H	1. All technicians are to follow the procedure detailed in SWP-04 - Working at Height. 2. Safety Harnesses are subject to a programme of formal inspection/replacement & should be visually inspected before each occasion of use.	1	4	L			

# **RISK ASSESSMENT**

<b>Assessment Title</b> (Task, process, equipment or facility)		<b>VNA-MAST REMOVAL-INSTALLATION</b>		<b>Location</b>	<b>Customer Premises/Toyota Workshops</b>
<b>Date</b>	<b>01/04/2026</b>	<b>Prepared By</b>	<b>R Lewis, M Ockwell</b>	<b>This is in addition to generic risk assessments available</b>	
<b>Review Date</b>	<b>31/03/2027</b>				
<b>Service Order Number/s</b>				<b>On Site Rules to be adhered to at all times</b>	
<p align="center"><b>Specific training is supplied via the TMHUK training Programmes</b></p> <p align="center"><b>Including: General H&amp;S, Working at Height, Use and Maintenance of Lifting Equipment &amp; Tools, Selection of Safe Working Area, Jacking &amp; Blocking, Use of PPE</b></p>					

Hazards. Identify all hazards from this activity. Select from the list below what could cause harm from this activity <i>E.G working at height, trip hazard. Etc</i>	Effect (Who/what may be harmed/damaged?)	Potential injury/effect sustained	Initial Risk			Current Control Measures <small>For each hazard, the measures taken by TMHUK to minimise the risk identified</small>	Risk <small>The level of risk once current controls are in place</small>			Additional Controls Measures <small>For each hazard, list any site specific measures you will be taking to further minimise the risk identified</small>	Action by whom?	Action by when?
			Likelihood	Severity	Risk Level		Likelihood	Severity	Risk Level			
Height - Working at & Falling objects	TMHUK Team Members / customer / 3rd party contractors / site visitors / property, equipment & environmental damage	Various injuries to the human physique / possibility of death	3	5	H	1. All technicians are to follow the procedure detailed in SWP-04 - Working at Height. 2. The safety of those working nearby is addressed by adherence to SWP "Work Area" for example, erection of barriers may be required to prevent unauthorised access. 3. Associated Risk Assessment WPRA-04 for Working at Height is in place and all technicians are to follow the control measures documented - the risk assessment is supported by SWP-04. 4. All other relevant SWP's & WPRA's should be observed and followed where appropriate. 5. Working at height must be avoided unless absolutely necessary, if unavoidable a further assessment may be required and further controls introduced. 6. PPE will be supplied and used in accordance with SWP-32 PPE, including a harness and lanyard.	1	5	L			
Jacking & Blocking	TMHUK employees / customer / 3rd party contractors / site visitors / property & equipment damage	Various injuries to the human physique / possibility of death	3	5	M	1. All technicians are to follow the procedure detailed in SWP-02 - Jacking & Blocking and refer to WPRA-02. 2. Truck manufacturers produce maintenance instructions for new equipment that contain instructions on safe jacking techniques which should be referred to in order to decide which jacking / blocking method is to be used. 3. Equipment jacked up will not be worked on unless suitable blocks are in position supporting the load.	1	4	L			

# RISK ASSESSMENT

<b>Assessment Title</b> (Task, process, equipment or facility)		<b>VNA-MAST REMOVAL-INSTALLATION</b>		<b>Location</b>	<b>Customer Premises/Toyota Workshops</b>
<b>Date</b>	<b>01/04/2026</b>	<b>Prepared By</b>	<b>R Lewis, M Ockwell</b>		<b>This is in addition to generic risk assessments available</b>
<b>Review Date</b>	<b>31/03/2027</b>				
<b>Service Order Number/s</b>					<b>On Site Rules to be adhered to at all times</b>
<p align="center"><b>Specific training is supplied via the TMHUK training Programmes</b></p> <p align="center"><b>Including: General H&amp;S, Working at Height, Use and Maintenance of Lifting Equipment &amp; Tools, Selection of Safe Working Area, Jacking &amp; Blocking, Use of PPE</b></p>					

Hazards. Identify all hazards from this activity. Select from the list below what could cause harm from this activity <i>E.G working at height, trip hazard. Etc</i>	Effect (Who/what may be harmed/damaged?)	Potential injury/effect sustained	Initial Risk			Current Control Measures <small>For each hazard, the measures taken by TMHUK to minimise the risk identified</small>	Risk <small>The level of risk once current controls are in place</small>			Additional Controls Measures <small>For each hazard, list any site specific measures you will be taking to further minimise the risk identified</small>	Action by whom?	Action by when?
			Likelihood	Severity	Risk Level		Likelihood	Severity	Risk Level			
Lifting Equipment - Incorrect use of	TMHUK employees / customer / 3rd party contractors / site visitors / property & equipment damage	Slips, trips, falls. Falling objects. Various injuries to the human physique.	4	4	H	1. Training will include "Safe Slings Practises" and any specific Work Instruction from the Master Service Manual. 2. All technicians are to follow the procedure detailed in SWP-06 - Use of Lifting Equipment. 3. Auditing of lifting equipment is a requirement under the company's documented QMS/Safety & Environmental systems and will be carried in accordance with SM-15 "Safety Auditing". 4. SM-25 "Work Equipment" outlines the company policy on the provisions and use of work equipment. 5. Procedure PA-12 "Maintenance of Work Equipment" is in place to enable continued efficient use of company supplied work equipment. 6. Procedure P6-05 "Thorough Examination of Lifting Equipment" is in place to provide the framework for dealing with the Thorough Examination of lifting equipment, lifting equipment accessories and the maintenance of records.	1	4	L	THIRD PARTY TO PROVIDE THEIR OWN RAMS PRIOR TO START OF WORK.CERTIFIED LIFTING EQUIPMENT SHOULD BE DELIVERED TO SITE PRIOR TO INSTALL.	CONTRACTOR	PRIOR TO INSTALL

# RISK ASSESSMENT

<b>Assessment Title</b> (Task, process, equipment or facility)		<b>VNA-MAST REMOVAL-INSTALLATION</b>		<b>Location</b>	<b>Customer Premises/Toyota Workshops</b>
<b>Date</b>	<b>01/04/2026</b>	<b>Prepared By</b>	<b>R Lewis, M Ockwell</b>	<b>This is in addition to generic risk assessments available</b>	
<b>Review Date</b>	<b>31/03/2027</b>				
<b>Service Order Number/s</b>				<b>On Site Rules to be adhered to at all times</b>	
<p align="center"><b>Specific training is supplied via the TMHUK training Programmes</b></p> <p align="center"><b>Including: General H&amp;S, Working at Height, Use and Maintenance of Lifting Equipment &amp; Tools, Selection of Safe Working Area, Jacking &amp; Blocking, Use of PPE</b></p>					

Hazards. Identify all hazards from this activity. Select from the list below what could cause harm from this activity <i>E.G working at height, trip hazard. Etc</i>	Effect (Who/what may be harmed/damaged?)	Potential injury/effect sustained	Initial Risk			Current Control Measures <small>For each hazard, the measures taken by TMHUK to minimise the risk identified</small>	Risk <small>The level of risk once current controls are in place</small>			Additional Controls Measures <small>For each hazard, list any site specific measures you will be taking to further minimise the risk identified</small>	Action by whom?	Action by when?
			Likelihood	Severity	Risk Level		Likelihood	Severity	Risk Level			
Manual handling	TMHUK Team Members	Various injuries to the human physique, musculoskeletal disorders	3	4	M	1. All staff are to follow the procedure detailed in SWP-13 - Manual Handling. 2. If the load is considered to be heavy or awkward then Safe Working Practice SWP-06 Use of Lifting Equipment must be followed in order to assist the lift. 3. Associated Risk Assessment WPRA-13 Manual Handling is in place & all team members are to follow the control measures documented - the risk assessment is supported by SWP-13.	1	4	L			
PPE - Non use of	TMHUK Team Members	Various injuries to the human physique / possibility of death	2	4	M	1. It is mandatory for all technicians to wear industrial shoes/boots / company overalls / Hi-Viz / Hard Hat / Harness & Lanyard/ safety goggles/ gloves / ear defenders. (SWP 32-PPE). 2. All technicians will adhere to the customers site procedure and instructions regarding PPE requirements.	1	4	L			
Slip, trips & falls	TMHUK Team Members	Various injuries to the human physique	3	3	M	1. All relevant SWP's & WPRA's should be observed and followed where appropriate. Particular attention must be given to SWP-01 Work Area. 2. Good housekeeping should be observed at all times. 3. Any spills must be cleaned up immediately.	1	3	L			

# RISK ASSESSMENT

<b>Assessment Title</b> (Task, process, equipment or facility)		<b>VNA-MAST REMOVAL-INSTALLATION</b>		<b>Location</b>	<b>Customer Premises/Toyota Workshops</b>
<b>Date</b>	<b>01/04/2026</b>	<b>Prepared By</b>	<b>R Lewis, M Ockwell</b>	<b>This is in addition to generic risk assessments available</b>	
<b>Review Date</b>	<b>31/03/2027</b>				
<b>Service Order Number/s</b>				<b>On Site Rules to be adhered to at all times</b>	
<p align="center"><b>Specific training is supplied via the TMHUK training Programmes</b></p> <p align="center"><b>Including: General H&amp;S, Working at Height, Use and Maintenance of Lifting Equipment &amp; Tools, Selection of Safe Working Area, Jacking &amp; Blocking, Use of PPE</b></p>					

Hazards. Identify all hazards from this activity. Select from the list below what could cause harm from this activity <i>E.G working at height, trip hazard. Etc</i>	Effect (Who/what may be harmed/damaged?)	Potential injury/effect sustained	Initial Risk			Current Control Measures <small>For each hazard, the measures taken by TMHUK to minimise the risk identified</small>	Risk <small>The level of risk once current controls are in place</small>			Additional Controls Measures <small>For each hazard, list any site specific measures you will be taking to further minimise the risk identified</small>	Action by whom?	Action by when?
			Likelihood	Severity	Risk Level		Likelihood	Severity	Risk Level			
Spillage / leakage	TMHUK Team Members / customer / 3rd party contractors / site visitors / environmental damage	Slips & exposure to sources of ignition. Acid burns / inhalation, Environmental impact.	3	4	M	1. All technicians are to follow procedure SM-29- Chemical Handling and SWP-19 - Spillages, in the event of a spillage. 2. Technicians will be supplied with the appropriate CoSHH data sheets & the relevant CoSHH risk assessment. 3. PPE will be supplied and used in accordance with SWP-32 PPE. 4. All technicians must have available a suitable spill kit.	1	4	L	ALL HOSES MUST HAVE BLANKING PLUGS FITTED	TECHNICIAN	INSTALL DAY
Tools - Use of	TMHUK Team Members	Various injuries to the human physique	2	3	L	1. All technicians are to follow the procedure detailed in SWP-11-Working with Electricity. 2. All tools will be subject to periodic inspection & testing. Any faulty, damaged or excessively worn tools must be removed from use and replaced or repaired immediately. 3. Electrical equipment will be used & maintained in accordance with SM-28 Electricity at Work. 4. Good housekeeping will be observed. 5. PPE will be supplied and used in accordance with SWP-32 PPE	1	3	L			

# **RISK ASSESSMENT**

<b>Assessment Title</b> (Task, process, equipment or facility)		<b>VNA-MAST REMOVAL-INSTALLATION</b>		<b>Location</b>	<b>Customer Premises/Toyota Workshops</b>
<b>Date</b>	<b>01/04/2026</b>	<b>Prepared By</b>	<b>R Lewis, M Ockwell</b>	<b>This is in addition to generic risk assessments available</b>	
<b>Review Date</b>	<b>31/03/2027</b>				
<b>Service Order Number/s</b>				<b>On Site Rules to be adhered to at all times</b>	
<p align="center"><b>Specific training is supplied via the TMHUK training Programmes</b></p> <p align="center"><b>Including: General H&amp;S, Working at Height, Use and Maintenance of Lifting Equipment &amp; Tools, Selection of Safe Working Area, Jacking &amp; Blocking, Use of PPE</b></p>					

Hazards. Identify all hazards from this activity. Select from the list below what could cause harm from this activity <i>E.G working at height, trip hazard. Etc</i>	Effect (Who/what may be harmed/damaged?)	Potential injury/effect sustained	Initial Risk			Current Control Measures <small>For each hazard, the measures taken by TMHUK to minimise the risk identified</small>	Risk <small>The level of risk once current controls are in place</small>			Additional Controls Measures <small>For each hazard, list any <b>site specific</b> measures you will be taking to further minimise the risk identified</small>	Action by whom?	Action by when?
			Likelihood	Severity	Risk Level		Likelihood	Severity	Risk Level			
Vehicle movement	TMHUK Team Members / customer / 3rd party contractors / site visitors / general members of the public / property & equipment damage	Various injuries to the human physique / possibility of death	3	5	H	1. On site rules will be adhered to at all times. 2. If a designated work area is not available then a temporary safe area should be constructed. Refer to SWP-01 Work Area. 3. If having to work in an aisle, where possible each end of the passageway should be closed off to pedestrians and vehicles. 4. All team members are to exercise extreme caution when passing through the warehouse & other transport routes - keep to the walkways where provided. 5. Avoid walking/driving around the rear of reversing vehicles. 6. Appropriate PPE is to be worn at all times i.e. Hi-Viz.	1	5	L			